


In-Stent Dissection Causes No Flow During Percutaneous Coronary Intervention



Fumiaki Yashima, MD, Shinsuke Yuasa, MD, PhD, Yuichiro Maekawa, MD, PhD, Mai Kimura, MD, PhD, Keitaro Akita, MD, Ryo Yanagisawa, MD, Makoto Tanaka, MD, Kentaro Hayashida, MD, PhD, Takashi Kawakami, MD, Hideaki Kanazawa, MD, PhD, Jun Fujita, MD, PhD, Keiichi Fukuda, MD, PhD

A 71-year-old woman with chest pain consulted us 1 week after an emergent operation for a small intestine perforation. She had previously undergone percutaneous coronary intervention (PCI) twice for the left anterior descending artery. The first was performed with a bare-metal stent 5 years earlier, and the second was performed for in-stent restenosis (ISR) treated with a biolimus A9-eluting stent. Angiography revealed 99% restenosis at the same location as that of the previous ISR (**Figure 1A**, [Online Video 1](#)); therefore, PCI was performed. Immediately after initial dilation using a

semicompliant 2.0-mm balloon, the coronary flow abruptly disappeared (**Figure 1B**, [Online Video 2](#)). The slow-flow/no-reflow phenomenon is associated with myocardial injury, less favorable clinical outcomes, and generally with microthromboemboli. Despite standard treatments such as manual thrombus aspiration and intracoronary vasodilator administration, we could not reestablish coronary flow. To determine the mechanism underlying the no flow, we performed intravascular ultrasound (IVUS), which did not reveal the cause of the no flow (**Figures 1D and 1E**, [Online Video 3](#)). We then




From the Department of Cardiology, Keio University School of Medicine, Tokyo, Japan. Dr. Hayashida is a proctor for transfemoral transcatheter aortic valve implantation for Edwards Lifesciences. All other authors have reported that they have no relationships relevant to the contents of this paper to disclose.

Manuscript received August 18, 2015; revised manuscript received September 9, 2015, accepted September 10, 2015.

performed optical coherence tomography, which clearly showed a dissection within the previous stent (Figures 1F to 1H, Online Video 4). Subsequent dilation by a cutting balloon re-established coronary flow (Figure 1I, Online Video 5). We speculated that neoatherosclerosis within the stent caused the restenosis, and the initial dilation induced a dissection that caused occlusion and resulted in no flow. This report is the first to show that in-stent dissection can cause no flow during PCI and that optical coherence tomography would uncover the mechanism.

REPRINT REQUESTS AND CORRESPONDENCE: Dr. Shinsuke Yuasa, Department of Cardiology, Keio University School of Medicine, 35 Shinanomachi, Shinjuku-ku, Tokyo 160-8582, Japan. E-mail: yuasa@keio.jp.

KEY WORDS no flow, in-stent restenosis, optical coherence tomography, percutaneous coronary intervention

 **APPENDIX** For supplemental videos, please see the online version of this article.